

## AMPHITHEATRE - TECHNICAL DETAILS AMIRAUTE HOTEL DEAUVILLE

**Sound Equipment** : Public Address system :JBL loudspeakers, Bose 100v FreeSpace 102F Loudspeaker, QSC 100v Line amplifier, Power amplifier C.Audio, Sound is routed through a BSS Soundweb DSP system controller. JBL monitor speakers, on stake and mobile. 4 JBL left and right speakers type SIM 200 watt. 8 Subwoofers JBL type S1S 400 watt, 2 JBL central speakers type S1C 200 W, JBL surround sound with THX AC3 DTS processor. 4 HF hand held SENNHEISER SKM 5000 microphones, frequency 750,600 à 773,500. K&M Telescopic mike stand with boom.  
32 channel monitor mixer ALLEN et HEATH GL 3300.

**Audio and Video equipment:** Tascam double cassette deck 202 MK3, Tascam High Resolution DA-45HR DAT recorder, PANASONIC A 360 DVD player, Yamaha SPX-1000 effects processor, LCD Proxima Pro AV 9310 Projector for video and computer display ( LCD screen 3" TFT active true XGA 1024x768 ; SXGA (1280 x 1024) via compression, output 2100 LUMENS ANSI), long focus zoom for DP 9310 PROXIMA, Extron 8 x 4 RS232 Matrix switcher A/RGBHV Extron 12 x 8 RS232 Matrix switcher A/V. Universal computer interface ANALOG WAY Splitter , Sony SP Betacam video recorder/playback, PANASONIC NV HS 900 VHS/S-VHS Video recorder, 1 x 10 VITY Stereo audio/video distributor.

**Screen:** Oray electric 6 m x4.5 m projection screen  
CD player: Sony 300 disc player

**Lighting** : 15 RVE 1kw shuttered spots, 10 RVE 1 kw PC floods 2 2kw RVE PC floods, 25 PAR 64 lamps.

Stage: 112 m<sup>2</sup> stage , rear and front of stage curtains  
Lighting console: 96 3Kw circuits by Light Technology

**Freight lift:** At back of stage

Length: 5.56m, Width: 2.40 m, Height : 2.10 m (L216in x W 94in xH82in)

Maximum load: 3 tonnes (6600 lbs)

At the centre back of the stage, (opening in the width direction)

Access to the lift via a locked garage (parking space for 2 vehicles)

Several vehicles or lorries can gain access in front of the garage

Fixed hoist total maximum weight 500 kg (1100 pounds) uniformly distributed

**112 square metre stage** (9,9m x 11,4m - 32ft8in X 37ft7in)

with a 6m x 4.5 m screen on mobile base.

All this equipment is included in the hire of the theatre, and will be exclusively operated by our technician from the fixed main control room. For all other equipment, a pre-wired extension control centre located at balcony level is available. Supplementary equipment can be hired from us subject to quotation.

For more precise details either on the equipment or the technical characteristics, you can contact Damien (Theatre technician) on +33 (0)2.31.81.82.83.